RECEIVED JAN 05 2018

Petersburg Borough, Alaska

Application to Lease or Purchase Real Property

(\$100.00 non-refundable filing fee required) PA VISA 1-5-18

Form must be completed in its entirety to be considered

Date of Application: TAN 4, 2018	Lease or Purchase Request? (circle appropriate choice)					
Parcel ID# of Subject Property:	Proposed term of lease: 5 RENEWA (total years) TNOUSTREAL Current Zoning of Property					
Applicant Name: ISLAND VEN TURES LLC						
Applicant Mailing Address: P.O. Box 966	To the control of the					
PETERSBURG, AL 992	833					
1. If the complete parcel described above is not being requisize of the parcel to be acquired in square feet	uested for lease/purchase, identify the					
2. Attach a map showing the location of the land requeste with the land requested clearly marked with bolded borders or high	d. Map must show surrounding area ghlighted color.					
3. Narrative on use of property: Explain proposed use of la and end. Include any planned new construction or renovation, in or renovation will be completed and type of materials to be used. proposed improvements. Explain the value of the proposal to the information you feel should be considered. (attached additional sheet Proposed USE IS FOR TEMPORARY BOHT ATTACHED IFOR DE TAKLS.	Provide the estimated dollar value of the economy of the city and any other if necessary)					
4. Name and address of all adjacent land owners or lesapplicable: (attach additional sheet if necessary) <u>PETEN 13,026 BORCOSH FOR ALL.</u>						

5.	Are t	here any exis	ting permits or l	eases covering	any part o	of the land a	applied for?	
		Yes				_Lease	Permit)	
	Desci permi	ribe the type ittee or lessee	of permit or leases:	se, if applicable	, and the	name and	last known a	address of the
6.			e or federal				proposed u	
7.	If app	licant is a co	rporation, provid	le the following	g informa	tion:		
	A.	Name, addı	ess and place of	incorporation:	PET	= NS BU 13	AR	
	В.	Is the corpo	oration qualified	to do business i	in Alaska	?: <u>×</u> Ye	sNo	
	C.	Name and a	address of reside	nt agent:	TOHN Y	NURGAS, A	, P.O.B. k 9983	x 966;
NOT	ICE TO	APPLICAN	NT(s):					
estim adver	ated cos tising a	sts of: a title and other co	red to deposit report, survey sts incidental t Clerk of the an	, legal fees, po to the processi	ostage, ro	ecording fe is applicat	es, public r ion. Appli	noticing and cant will be
16.12 requir applic	and 16 rements ant.	.16 (as they . I furthe	ave received an may pertain t r certify I am	o my particul authorized to	ar applic o sign t	eation) and his applica	d understan ation on be	d the Code chalf of the
					Ā	pplicant/Ap	m Muyaz oplicant's Re	presentative
Subsci	ribed an	d sworn to be	efore me this	57th d	ay of <u></u>	anuar	1, 20 <u>18</u> ;	
•			efore me this			Star	ing J.	otary Public
			d for the State of					
				OF ALASH OFFICIAL SEAL Stacy Luhr OTARY PUBLIC Immission Expires			,	2/12

<u>DESCRIPTION</u> Island Ventures LLC proposes to install, at its expense, including USACE permit(s), a temporary boat ramp using personal property crushed rock, adjacent to and north of the present spit at the Scow Bay Turnaround, approximately 250 feet south of the present ramp. Applicant assumes there will be non monetary cooperation from property owner Petersburg Borough to obtain the USACE permit(s). Surface dimensions would be 24 feet width by 170 feet length. Overall width including shoulder would average 32 feet (34 feet at top, 30 feet at bottom). Construction native ground up would be geotech cloth, 2 to 8 feet pit run crushed rock, compacted 3 inch minus rock on surface, barrier rock on south shoulder as needed. The ramp would be "temporary" in the sense the area would be completely buried by the Petersburg Borough when and if the Borough moves forward with planned expansion of the Scow Bay Turnaround facility, or for any other public purpose. When and if the lease is terminated the personal property crushed rock would be removed by lessee Island Ventures LLC, unless mutually agreed otherwise by lessor Petersburg Borough and lessee Island Ventures LLC.

<u>PURPOSE</u> The purpose of the ramp is to improve the ability to launch and haul boats when there are prevailing southerly winds and waves. The existing jetty provides excellent protection from those conditions.

<u>COST/BENEFIT</u>, <u>SAFETY</u>, <u>MAINTENANCE</u> Although the temporary life span of the proposed ramp may be short (estimated at 2 to 10 years depending on grant funds for the total Scow Bay project), cost/benefit is still worthwhile. Increased safety offered by the proposed ramp would reduce liability for the Petersburg Borough. The ramp would be maintained by Island Ventures LLC.


<u>SCHEDULE</u> USACE permit is estimated to take 3 to 6 months, if granted. Lease requirements would begin once the USACE permit(s) is issued. If not issued, the project would be cancelled. Construction is estimated to be completed within 6 months after the USACE permit is issued, excluding winter months December through March, or any other periods disallowed by government agencies for habitat or environmental reasons. Actual construction time is estimated 3 days.

BENEFIT TO COMMUNITY Boat launching ramps are vital to all communities in SE Alaska. On a per capita basis, Petersburg has less than the average number of ramps in its main population area. The present Scow Bay ramp receives much use, both commercial and pleasure. An additional ramp that allows safe use in prevailing southerly winds would be beneficial to the community. General private use of the ramp would be allowed on an individual permission


basis with supervision by Island Ventures LLC when staff is available. The proposed ramp would help keep commercial vessel services in Petersburg instead of going to other communities.

FAVORABLE RAMP SLOPE Ramp slope of 5 degrees is the maximum slope for a large vessel hydraulic trailer without potential vessel sliding. It is minimally adequate for most recreational vessels. The present Scow Bay ramp slope is 5 degrees only on the upper concrete portion, then tapers (banana shaped) to 4 and 3 degrees, so is useable for recreational boats only at its upper portion. The proposed ramp is designed to provide a more constant slope, which will allow a larger launch tide window for recreational vessels.

OTHER Geotechnical data is favorable. See attached test pit data. The adjacent spit, installed in the 1960's, has not settled. Tidal current, at all stages of tide, is zero. Wave erosion of beach rock and sands, and littoral drift erosion, are close to zero. Maintenance of surface 3 inch minus compacted rock is expected to be minimal. There would be no loss of traction nor compromise of surface competency of the rock ramp vs. a concrete ramp. Island Ventures LLC has been operating on the rock portion of the present ramp with minimal maintenance since 2007.



PURPOSE:	EXISTING CONDITIONS	SCOW BAY BOAT HAULOUT
TEST PIT INVESTIGATION	SCALE IN FEET	
HTL = 19.5°	20 SCALE	APPLICANT: CITY AND BOROUGH PETERSBURG, ALASKA FILE NO.: WATERWAY: WRANGELL NARROWS PROPOSED ACTIVITY: TEST PIT INVESTIGATION SEC. 4 T. 59 S R. 79 E M COPPER RIVER MERIDIAN LAT.: 56.7806' N LONG.: 132.9730' W
DATUM: MHW = 14.8' MLLW = 0.0' MLLW = 0.0'	PND PROJECT NO. 162046.01	LAT.: 56.7806' N LONG.: 132.9730' W DATE: MARCH 2017 SHEET 1 of 1





SOILS CLASSIFICATION, CONSISTENCY AND SYMBOLS

CLASSIFICATION

Identification and classification of the soil is accomplished in general accordance with the ASTM version of the Unified Soil Classification System (USCS) as presented in ASTM Standard D2487. The standard is a qualitative method of classifying soil into the following major divisions (1) coarse grained, (2) fine grained, and (3) highly organic soils. Classification is performed on the soils passing the 75 mm (3 inch) sieve and if possible the amount of oversize material (> 75 mm particles) is noted on the soil logs. This is not always possible for drilled test holes because the oversize particles are typically too large to be captured in the sampling equipment. Oversize materials greater than 300 mm (12 inches) are termed boulders, while materials between 75 mm and 300 mm are termed cobbles. Coarse grained soils are those having 50% or more of the non-oversize soil retained on the No. 200 sieve (0.075 mm); if a greater percentage of the coarse grains is retained on the No. 4 (4.76 mm) sieve the coarse grained soil is classified as gravel, otherwise it is classified as sand. Fine grained soils are those having more than 50% of the non-oversize material passing the No. 200 sieve; these may be classified as silt or clay depending their Atterberg liquid and plastic limits or observations of field consistency. Refer to the most recent version of ASTM D2487 for a complete discussion of the classification method.

SOIL CONSISTENCY - CRITERIA

Soil consistency as defined below and determined by normal field and laboratory methods applies only to non-frozen material. For these materials, the influence of such factors as soil structure, i.e. Fissure systems, shinkage cracks, slickensides, etc., must be taken into consideration in making any correlation with the consistency values listed below. In permafrost zones, the consistency and strength of frozen soils may vary significantly and unexplainably with ice content, thermal regime and soil type.

Standard Penetration Test (Blows/ft) Relative to Density/Consistency

N60	Density	Relative Density	N60	Consistency	Undrained Shear Strength psf	
0-4	Very Loose	0-15%	< 2	Very Soft	< 250	
4-10	Loose	15-35%	2 - 4	Soft	250 - 500	
10-30	Medium	35-65%	4 - 8	Medium	500 - 1000	
30-50	Dense	65-85%	8 - 15	Suff	1000 - 2000	
> 50	Very Dense	>85%	15 - 30	Very Stiff	2000 - 4000	
			> 30	Hard	> 4000	

Ref: Terzaghi, Peck, and Mesri Soil Mechanics in Engineering Practice, 3rd Edition, pg 60-63
ASTM D1586 Standard Test Method for Penetration Test and Split-Barrel Sampling of Soils
ASTM D2487 Standard Practice for Classification of Soils for Engineering Purposes (USCS)

SAMPLER TYPE SYMBOLS

A Bs Cs	Auger Sample Bulk (grab) Sample Core Barrel w/ Single Tube	Hs Pb Si	1.4" Split Spoon w/ Air Hammer Pitcher Barrel 2.5" Split Spoon w/ 140# Hammer	Ss St Sx	1.4" Split Spoon w/ 140# Hammer 1.4" Split Spoon w/ 47# Hammer 2.0" Split Spoon w/ 47# Hammer
Cd	Core Barrel w/ Double Tube	Sm	2.5" Split Spoon w/ 300# Hammer	Sz	1.4 Split Spoon w/ 340# Hammer
Ct	Core Barrel w/ Triple Tube	Sh	2.5" Split Spoon w/ 340# Hammer	Ts	Shelby Tube
HI	2.5" Split Spoon w/ Air Hammer	Sp	2.5" Split Spoon, Pushed	Tm	•

Note: Split Spoon size refers to sampler inside diameter.

P N D	Designed: PND Drawn: PND Checked: PND	STANDARD BOREHOLE LOG DETAILS					
ENGINEERS, INC.	Project No.: 162046311 Date: March 2017	BOREHOLE LOGS	FIGURE A 1 of 3				

		SOIL/ROCK DESCRIPTION		,		SAMI	PLES	GRAPH COMMENTS	
Depth (Feet) Water Table	GRAPHIC SYMBOL	Soil Name, Color, Moisture Condition, Relative Density, Soil Structure, Mineralogy, Other Information Rock Name, Description	Number	Tipe	Location	Recovery (%) (RQD)	Penetration Blows per 6/Inch (per Font)* or {Rock Quality}	2 4 6 8 Additional information	Elevation (Feet)
- - - * - 2	00000	0' - 0.30' A.C. PAVEMENT POORLY-GRADED GRAVEL W/ SILT AND SAND (GP-GM) Gray, Moist, Dense, Subangular	1	Ss		30	20-20-25 (45)	Begin drilling 10/24/03 8:00 2.m. 1.5' to 2' · Hard, loud drilling (Cobbles/Boulder encountered)	24.43 — — — .43 —
_		SLATY ARGILLITE, grayish black, fine grained, thin bedded, medium hard, BX-U, steeply dipping	2	Ct		56 (50)	{Poor}	drillhole blockage	
12	3	4	5	6	7	8	9	10 11 12	2

COLUMN DESCRIPTIONS

ſ	7	Depth	Danels (in time) below sharement with in
L	ı	nehm	Depth (in feet) below the ground surface.

- 2 Water Level Groundwater level recorded while drilling. Depths and times are recorded in comments column.
- 3 Graphic Log Graphic depiction of materials encountered.
- Soil/ Rock Description of materials encountered, including USCS soil descriptions and rock descriptions defined in Fig. B-5 and B-6.
- 5 Sample Number Sample identification number.
- 6 Sample Type of soil or rock sample collected at depth interval depicted; symbols explained on Fig. B-1.
- [7] Sample Location Location of soil or rock sample taken.
- 8 Sample Recovery Soil: Percentage of sample recovered, Rock: Percentage of sample recovered and RQD value.
- Sample Blows or Rock Quality

 Soil: Number of blows to advance driven sampler each 6-inch interval using sampler type specified with a 30-inch drop. Blows per foot given in parentheses. Rock: Rock quality as defined from RQD value.
- Graphs Graphic log depicting blow counts per foot with a specified split spoon, Pocket Penetration and Vane Shear tests depicted where taken on fine grained soils.
- [11] Comments Comments or observations on drilling/sampling by driller or PND field personnel.
- [12] Elevation Elevation (in feet) with respect to Mean Lower Low Water (MLEW) or other datum where specified.

GENERAL NOTES

- 1. Field descriptions may have been modified to reflect laboratory test results.
- Descriptions on these boring logs apply only at the specific locations at the time the borings were drilled. They are not warranted to be representative of subsurface conditions at other locations or times.
- Split spoon blow counts shown are uncorrected raw data. Various hammer sizes and split spoon sizes were used and have not been
 corrected to a Standard Penetration Test (SPT). Blow counts may vary substantially between SPT and these methods.

P N D	Designed: PND Drawn: PND Checked: PND	STANDARD BOREHOLE LOG DETAILS					
ENGINEERS, INC.	Project No.: 162046,01 Date: March 2017	BOREHOLE LOGS	FIGURE A 2 of 3				

Soil Legend

M	AJOR DIVISIO	าทร	SYM	BOLS	TYPICAL
,,,,			GRAPH	LETTER	DESCRIPTIONS
	GRAVEL AND	CLEAN GRAVELS		GW	Well-graded gravels, gravel sand mixtures, little or no fines
COARSE GRAINED	GRAVELLY	ELITE DE NO SINÉS!		GP	Poorly graded gravels, gravel-Sand mixtures, little or no fines
SOILS	MORE THAN 50% OF COARSE FRACTION RETAINED ON NO.	GRAVELS WITH FINES	1000 10000 100000	GM	Slity gravels, gravel-sand-slit mixtures
	4 SIEVE (4.75mm)	(APPRECIABLE AMOUNT OF HALS)		GC	Clayey gravels, gravel-sand-clay mixtures
	SAND AND	CLEAN SANDS		sw	Well-graded sands, gravely sands, little or no lines
MORE THAN 50% RETAINED ON NO.	SANDY SOILS	(RLIT ON NO LINES!		SP	Poorly graded sands, gravelly sands, little or no fines
200 SIEVE (0.075mm)	MORE THAM 50% OF COARSE FRACTION PASSING NO. 4	SANDS WITH FINES		SM	Silty sands, sand-silt mixtures
	SIEVE (4.75mm)	Objust) (Tabalcivari vivoral		sc	clayey sands, sand-clay mixtures
gu) (g	4			ML	inorganic silts and very fine sands, rock flour, siky or clayey fine sands or clayey silts with slight plasticity
FINE GRAINED SOILS	SILTS AND CLAYS	LIQUIDERMIT LESS THAN 50		CL	inorganic clays of low to medium plasticity gravelly clays, sandy clays, silty clays, lean clays
				OL	Organic silts and organic silty clays of low plasticity
	CH TC			МН	Inorganic silts, releaceous or diatomiceous fine sandy or silty soils, elastic silts
MORE THAN 50% PASSING NO. 200 SIEVE (0.075mm)	SILTS AND CLAYS	uquib umit Griater in an 50		СН	Inorganic clays of high plasticity, fat clays
				ОН	Organic clays of medium to high plasticity, organic sits
ніс	HLY ORGANIC SO	ILS J	7 22 25 28 28 4	PT	Peat and other highly organic solls

NOTE: Multiple symbols are used to indicate borderline or dual soil classifications as per ASTM 2488

Stratigraphic Contact Distinct contact between soil strata or geologic units Approximate location of soil strata change within a geologic soil unit Laboratory / Field Tests List of Abbreviations .%F Percent Fines НΑ Hydrometer Analysis PР Pocket Penetrometer ΑL Atterberg Limits LMA Limited Mechanical Analysis SA Sieve Analysis CP Laboratory Compaction test MC Moisture Content TV Torvane CO Consolidation test MD Moisture content and Dry density ΤX Triaxial Shear DP Depth "Peat" Probe OC Organic Content UC **Unconfined Compression** DS Direct Shear PMPermeability or Hydraulic Conductivity VS Vane Shear Designed: PND STANDARD BOREHOLE Drawn: מאיז LOG DETAILS Checked: PND Project No.: 162046.01 ENGINEERS, INC. FIGURE A **BOREHOLE LOGS** Date: March 2017 3 of 3

-		SOIL DESCRIPT	ION !		S	AMI	LES		GI	RAP	Н		COMMENTS	
Depth (feet)	Graphic Symbol	Soil Name, Color, Moistu Content, Relative Density Soil Structure, Mineralog Other Information	re /, y.	Number	Type Location	Recovery % (RQD %)	Penetration Blows per 6/Inch (per foot) or (Rock Quality)	20 P	OCKI 2 ANE	O 64 ET PE) 80 1 (usi) R (usi)		Casing Depth, Drilling Rate, Fluid Loss, Drill Pressure, Tests, Instrumentation, Additional Information	Elevation (feet)
		SAND WITH SILT AND GRAVEL (SM) gray and brown, medium densi imported fill	e: , ,	S	Bs			- 			;		Begin Excavation: 3/30/17; Time: 2:05pm Excavator Model PC 200-6 with 1.5 CY bucket	22.0-
- - 2.5 -	200°C	SILTY GRAVEL WITH SAN AND COBBLES (GM) bluish gray, dense to very dens glacial till	i					* *************************************			: .			19.5 -
5.0														17,0-
7.5)		Till walls hold firm											2ft. to 14ft.: hard excavating	14.5 -
- 10.0 0	7,0000 7,000													12.0
- 12.5 0 0 0 0 0 0 0 0 0	7,007							: :						9.5
-15.0		Test Pit Bottom						:					End Excavation: 3/30/17; Time: 2:25pm	7.0 -
17.5		·							•					4.5 -
-20.0														 2.0
P		Logged Doin Ent	try: PJO				SCC	W	B.A.	Y ers	BC bur	A g,	T HAULOUT Alaska	
	1	, 1	No.: 162048 Mar. 2		- 1		TEST	PIT	' T	P-7	7		FIGURE 7	



Photo 1: Begin excavation at TP1.



Photo 3: Greenish gray colored silty sand sits adjacent mound of bluish gray till clumps to the right at TP1.




Excavating through surface horizon of silty sand at TP2.



Photo 2: Excavating into glacial till at TP1.



Photo 4: Excavator en route over tide flats to TP2.



Upper silty sand horizon readily sloughs while lower wall within glacial till holds firm at TP2.





ENGINEERS, INC.